

COUNTY

Clarion

MUNICIPALITY

Clarion County

PROJECT #

17-16000-001

SUPERPAVE ASPHALT MIXTURE DESIGN

LOCATION OF WORK	FROM	TO	L E N G T H	W I D T H	D E P T H	SQ. YD.	TONS	MIX in mm	PERF. GRADE	CYCLES GRA	MATERIAL TYPE	REMARKS
Administration Drive	Merle Road	Merle Road	235	24.0	2.50	627	94	19.0	PG 64-22	50	BINDER 19.0	As Directed.
Administration Drive	Merle Road	Merle Road	235	24.0	1.50	627	56	9.5	PG 64-22	50	WEARING 9.5	As needed for tie in.
Administration Drive	Merle Road	Merle Road	75	10.0	2.50	83	13	19.0	PG 64-22	50	BINDER 19.0	As needed for tie in.
Administration Drive	Merle Road	Merle Road	75	10.0	1.50	83	8	9.5	PG 64-22	50	WEARING 9.5	As needed for tie in.
County Building	Parking	Area	95	24.0	2.50	253	38	19.0	PG 64-22	50	BINDER 19.0	As Directed.
County Building	Parking	Area	62	38.0	2.50	262	39	19.0	PG 64-22	50	BINDER 19.0	As Directed.
County Building	Parking	Area	18	17.0	2.50	34	5	19.0	PG 64-22	50	BINDER 19.0	As Directed.
County Building	Parking	Area	28	18.0	2.50	56	8	19.0	PG 64-22	50	BINDER 19.0	As Directed.
County Building	Parking	Area	95	24.0	1.50	253	23	9.5	PG 64-22	50	WEARING 9.5	As Directed.
County Building	Parking	Area	62	38.0	1.50	262	24	9.5	PG 64-22	50	WEARING 9.5	As Directed.
County Building	Parking	Area	18	17.0	1.50	34	3	9.5	PG 64-22	50	WEARING 9.5	As Directed.
County Building	Parking	Area	28	18.0	1.50	56	5	9.5	PG 64-22	50	WEARING 9.5	As Directed.
County Building	Parking	Area	28	18.0	1.50	56	5	9.5	PG 64-22	50	WEARING 9.5	As Directed.

COUNTY

Clarton

MUNICIPALITY

Clarton Cx

PROJECT # 17-16000-001

PRIME COAT

LOCATION OF WORK	FROM	TO	L E N G T H	W I D T H	SQ.YD.	OIL TYPE	GAL. OIL	REMARKS
Circle Drive Circle Drive Lengths used to insure proper coverage	Merle Road Parking	Merle Road Area	394 227	24.0 24.0	1,051 605	E-1 Prime E-1 Prime	315 182	0.50 Gal/SY-As Directed. 0.50 Gal/SY-As Directed.
TOTALS								1,656 497